



राष्ट्रीय विज्ञान शिक्षा एवं अनुसंधान संस्थान, भुवनेश्वर  
(परमाणु उर्जा विभाग, भारत सरकार का एक स्वयं शासित संस्थान)  
**NATIONAL INSTITUTE OF SCIENCE EDUCATION AND RESEARCH, BHUBANESWAR**  
(AN AUTONOMOUS INSTITUTE UNDER DEPT. OF ATOMIC ENERGY, GOVT. OF INDIA)

**Tender Notice**

NIT No. NISER/ IWD-Civil/Services/2017/29

Dated: 02.02.2018

Director, NISER hereby invites item rate tender in two parts for the following work of **“Providing & Laying Underground Hume pipe for Cable Crossing in NISER Campus, Jatni”** from contractors of CPWD/MES/Railways/State PWDs and/or those who have worked for DAE or its Organizations or Govt. /Semi Government organizations and have successfully carried out a minimum of one/two/three similar works of 80%/60%/40% respectively of the estimated cost or above as indicated below, during the last seven years. The eligible contractors may submit their bid along with supporting documents of fulfilling the above conditions otherwise the bids bear the risk of not being considered. The eligible contractors are also required to submit the self-attested copies of PAN Card, Registration and GST Registration certificate.

In support of fulfilling all the essential conditions mentioned in the previous Para the contractor shall submit the past details, mentioning the name of work, estimated cost, tendered amount, gross value of work done, date of commencement as per agreement & actual date of completion as per agreement along with schedule of quantities executed and any penalty levied due to delay in executing the work from an officer not below the rank of Executive Engineer (Civil).


Estimated Cost	EMD	Performance Security	Security Deposit	Time of completion
Rs.14,16,976.00	Rs.28,340.00	@ 5% of tendered amount	A sum @ 5% of the gross amount of the bill shall be deducted from each running bill till the sum amounts to Security Deposit @ 5% of the tendered amount of the work.	45 days from the date of receipt of acceptance letter/ submission of PG

Tender can be downloaded and bided from website address: [www.tenderwizard.com/NISER](http://www.tenderwizard.com/NISER). Tender documents for viewing only are also available in NISER website address: [www.niser.ac.in](http://www.niser.ac.in). The **tender cost of Rs. 500.00 & EMD of Rs. 28, 340.00**, separately in the form of A/C payee DD/ Banker's cheque drawn on any scheduled Bank, in favor of **Director, NISER**.

The tender documents are to be submitted in two parts (Technical & Financial Bid). Self-attested documents in support of eligibility criteria of the contractor, Technical bid, tender cost and EMD are to be uploaded online. The second part with scheduled items of work & price quoted are to be uploaded in prescribed format as Financial Bid. The bidders those who are applied online have to submit the hard copies along with original documents mentioned in NIT on or before **23 February, 2018 upto 3.45 PM and Technical bid will be opened at 04.00 PM on 23<sup>th</sup> February, 2018**. Those who qualify the technical bid shall be intimated later mentioning the date of opening of the financial bid.

Director, NISER, reserves the right to accept/reject any/all tenders without assigning any reason whatsoever. Part or incomplete tenders will be summarily rejected. No further correspondences whatsoever shall be entertained in this regard. Canvassing in any manner shall result in rejection of the tender.

Any dispute arising out of this shall subject to Bhubaneswar jurisdiction only.

  
Registrar, NISER

**Bill of Quantities**  
**Providing & Laying Underground Humepipe for Cable Crossing in NISER Campus, Jatni**

Sl. No.	Description of Items	Unit	Quantity	Rate	Amount
1	Excavation of road/earth/pavement by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth/road/pavement lead upto 50 m and lift upto 3.0 m, as directed by Engineer-in-charge.	Cu M	315.00		
2	Taking out existing kerb stones of all types from footpath/ central verge, including removal of mortar etc., disposal of unserviceable material to the dumping ground, stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	Metre	21.00		
3	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	Sq M	60.00		
4	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	Cu M	90.00		
5	Providing and laying Non Pressure NP-3 class (Medium duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete. 300 mm dia RCC pipes.	Metre	282.00		
6	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	Cu M	173.00		
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6 (1 Cement : 3 coarse sand (zone-III) : 6 graded stone aggregate 20 mm nominal size).	Cu M	14.00		
8	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	800.00		
9	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	Cu M	54.00		
10	Laying old cement concrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge. (Old CC paver blocks shall be supplied by the department free of cost).	Sq M	60.00		
11	Laying at or near ground level old kerb stones of all types in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement : 3 coarse sand), including making joints with or without grooves (thickness of joints, except at sharp curve, shall not be more than 5 mm), including making drainage opening wherever required etc. complete as per direction of Engineer-in-charge. (Length of finished kerb edging shall be measured for payment). (Old kerb stones shall be supplied by the department free of cost)	Metre	21.00		
12	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	200.00		
13	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	Cu M	13.00		
14	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand)	Sq M	110.00		
15	Cutting holes up to 45*45 cm in R.C.C. floors/wall/roof for passing drain pipe etc. and repairing the hole after insertion of drain pipe etc. with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), including finishing complete so as to make it leak proof.	Each	16.00		

16	Providing, hoisting and fixing above plinth level up to floor five level precast reinforced cement concrete work in string courses, bands, copings, bed plates, anchor blocks, plain window sills and the like, including the cost of required centering, shuttering but, excluding cost of reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size).	Cu M	2.00		
17	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kinds of soil	Sq M	1100.00		
			Total		