



राष्ट्रीय विज्ञान शिक्षा एवं अनुसंधान संस्थान, भुवनेश्वर

(परमाणु उर्जा विभाग, भारत सरकार का एक स्वयं शासित संस्थान)

NATIONAL INSTITUTE OF SCIENCE EDUCATION AND RESEARCH, BHUBANESWAR

(AN AUTONOMOUS INSTITUTE UNDER DEPT. OF ATOMIC ENERGY, GOVT. OF INDIA)

Name of Work: - Provision of Dry wall partition and aluminum partition for CIS department at Library Building, NISER, Jatani.

Notice Inviting E-Tender No. - NISER/ IWD-Civil/Academic/2019-20/09, Dated: 29.07.2019.

Estimated Cost of Tender: - Rs 14, 86, 647.00

Completion Time: - 60 days

Earnest Money : - Rs.29, 733.00

Cost of tender (non-refundable):- Rs. 500.00 (Rupees Five Hundred Only).

NOTE:

1. The details of tender notification can be downloaded from www.tenderwizard.com/NISER under "**Tender Free View**" link.
2. Vendors should obtain the USER ID and PASSWORD from www.tenderwizard.com/NISER by clicking on "**REGISTER ME**" link in the homepage.
3. The Vendor registration fees has to be paid to ITI Ltd for Rs. 1180/-. Using the e-payment link provided at the time of registration, and the mode of payments are Credit Card, Debit Card and Internet Banking. Vendor Registration is Valid for 1year.
4. For further details on e-Tender participation, please contact ITI Help desk on
 - Telephone: 080-49352000/9686115318
 - Email: harishkumar.kb@etenderwizard.com, ambasa@etenderwizard.com.
5. Tenders should be submitted only through e-Tender portal and obtain the Tender Acknowledgement copy as a proof of successful submission.



राष्ट्रीय विज्ञान शिक्षा एवं अनुसंधान संस्थान, भुवनेश्वर
(परमाणु उर्जा विभाग, भारत सरकार का एक स्वयं शासित संस्थान)
NATIONAL INSTITUTE OF SCIENCE EDUCATION AND RESEARCH, BHUBANESWAR
(AN AUTONOMOUS INSTITUTE UNDER DEPT. OF ATOMIC ENERGY, GOVT. OF INDIA)

TENDER DOCUMENTS

Notice Inviting E-Tender No. - NISER/ IWD-Civil/Academic/2019-20/09, Dated: 29.07.2019

Name of work: "Provision of Dry wall partition and aluminum partition for CIS department at Library Building, NISER, Jatani."

I N D E X

Sl. No.	Particulars	Remarks
1.	Particulars of Contractor	
2.	Eligibility Criteria	
3.	Abstract of general terms and conditions	
4.	Checklist of documents	
5	Experience of Contractor	

NOTE: Tender can be downloaded and bided from website address: www.tenderwizard.com/NISER. Tender documents for viewing only are also available in NISER web-site address: www.niser.ac.in

SIGNATURE OF THE OFFICER ISSUING TENDER

NAME OF THE WORK

Provision of Dry wall partition and aluminum partition for CIS department at Library Building, NISER, Jatani.

NOTE

The tenderer should enclose the following documents along with the Technical Bid otherwise tender will be summarily rejected.

- 1)
 - a) Scanned copy of self-attested works completion certificate during the last seven years from Govt./Semi- Govt. organization not below the rank of E.E as per NIT.
 - b) Scanned copy of self-attested valid Registration Certificate.
 - c) Scanned copy of self-attested PAN card.
 - d) Scanned copy of self-attested GST Registration certificate.
 - e) Scanned copy of the cost of tender paper for the bidders and EMD amount in separate D.D's as per NIT.
 - f) **Scanned copy of EPFO registration certificate.**
- 2) Also, contractors shall submit the above documents (self-attested) with original for verification before opening of technical bid for verification with original DD for EMD and cost of tender. The bidder those who will not submit the self-attested hard copies of required documents in the office, the technical bid of the bidder will not be opened.
- 3) Incomplete/Partial bid or bid not submitted in prescribed format will be rejected.



राष्ट्रीय विज्ञान शिक्षा एवं अनुसंधान संस्थान, भुवनेश्वर
(परमाणु उर्जा विभाग, भारत सरकार का एक स्वयं शासित संस्थान)
NATIONAL INSTITUTE OF SCIENCE EDUCATION AND RESEARCH, BHUBANESWAR
(AN AUTONOMOUS INSTITUTE UNDER DEPT. OF ATOMIC ENERGY, GOVT. OF INDIA)

NOTICE INVITING TENDER

Director, NISER invites online tender on single bid system for the following work:-

NIT No. NISER/ IWD-Civil/Academic/2019-20/09,

Dated: 29.07.2019

Name of the Work: - **Provision of Dry wall partition and aluminum partition for CIS department at Library Building, NISER, Jatani.**

Estimated Cost	:	Rs 14, 86, 647.00
Earnest Money	:	Rs.29, 733.00
Time of Completion	:	60 Days
Cost of tender (non-refundable)	:	Rs. 500.00 (Rupees Five Hundred Only)

Tender can be downloaded and bided from website address: www.tenderwizard.com/NISER.
Tender documents for viewing only are also available in NISER website address: www.niser.ac.in

Last date of submission of tender (online): 08 August, 2019 up to 12.30 PM.

Original EMD & Tender Paper cost submission at Office: 08 August, 2019 upto 3.45 PM.

Tender Opening date : 08 August, 2019 at 04.00 PM.

Faculty In Charge
Institute Works Department, NISER



राष्ट्रीय विज्ञान शिक्षा एवं अनुसंधान संस्थान, भुवनेश्वर
(परमाणु उर्जा विभाग, भारत सरकार का एक स्वयं शासित संस्थान)
NATIONAL INSTITUTE OF SCIENCE EDUCATION AND RESEARCH, BHUBANESWAR
(AN AUTONOMOUS INSTITUTE UNDER DEPT. OF ATOMIC ENERGY, GOVT. OF INDIA)

Tender Notice

NIT No. NISER/ IWD-Civil/Academic/2019-20/09,

Dated: 29.07.2019

Director, NISER hereby invites item rate single bid tender for the work **“Provision of Dry wall partition and aluminum partition for CIS department at Library Building, NISER, Jatani”** from contractors of CPWD/MES/Railways/State PWDs and/or those who have worked for DAE or its Organizations or Govt. /Semi Government organizations and have successfully carried out a minimum of one/two/three similar works of 80%/60%/40% respectively from any of the aforesaid organizations of the estimated cost or above as indicated below, during the last seven years. The eligible contractors may submit their bid along with supporting documents of fulfilling the above conditions otherwise the bids bear the risk of not being considered. The eligible contractors are also required to submit the self-attested copies of PAN Card, Registration, GST Registration certificate and **EPFO registration certificate**.

In support of fulfilling all the essential conditions mentioned in the previous Para the contractor shall submit the past details, mentioning the name of work, estimated cost, tendered amount, gross value of work done, date of commencement as per agreement & actual date of completion as per agreement along with schedule of quantities executed and any penalty levied due to delay in executing the work from an officer not below the rank of Executive Engineer (Civil).

Estimated Cost	EMD	Performance Security	Security Deposit	Time of completion
Rs.14,86,647.00	Rs.29,733.00	@ 5% of tendered amount	A sum @ 2.5% of the gross amount of the bill shall be deducted from each running bill till the sum amounts to Security Deposit @ 2.5% of the tendered amount of the work.	60 days from the date of receipt of work order.

Tender can be downloaded and bided from website address: www.tenderwizard.com/NISER. Tender documents for viewing only are also available in NISER website address: www.niser.ac.in. The **tender cost of Rs. 500.00 & EMD of Rs. 29,733.00**, separately in the form of A/C payee DD/ Banker's cheque drawn on any scheduled Bank, in favor of **Director, NISER**.

The tender documents are to be submitted in single bid. Self-attested documents in support of eligibility criteria of the contractor, tender cost and EMD are to be uploaded online. The second part with scheduled items of work & price quoted are to be uploaded in prescribed format as Financial Bid. The bidders those who are applied online have to submit the hard copies along with original documents mentioned in NIT on or before **08 August, 2019 upto 3.45 PM and Tender will be opened at 04.00 PM on 08 August, 2019**.

Director, NISER, reserves the right to accept/reject any/all tenders without assigning any reason whatsoever. Part or incomplete tenders will be summarily rejected. No further correspondences whatsoever shall be entertained in this regard. Canvassing in any manner shall result in rejection of the tender.

Any dispute arising out of this shall subject to Bhubaneswar jurisdiction only.

Faculty In Charge
Institute Works Department, NISER

General Terms and Conditions:

1. Online item rate tenders are hereby invited for the work of **“Provision of Dry wall partition and aluminum partition for CIS department at Library Building, NISER, Jatani”**. The estimated cost of work is **Rs. 14, 86,647.00**. The Earnest Money Deposit is **Rs. 29,733.00**. Contractors of CPWD/MES/Railways/State PWDs and/or those who have worked for DAE or its units or in any Govt./Semi Govt. organizations and have successfully carried out minimum one/two/three similar work of 80%/60%/40% respectively from any of the aforesaid organizations of the estimated cost and above during the last seven years, The eligible contractors may submit their bid along with supporting documents of fulfilling the above conditions otherwise their bids bear the risk of not being considered. **The contractors those who are applied online also required to submit the self-attested copies of PAN CARD, registration, GST registration certificate, EPFO registration certificate, EMD (Original) & Tender Paper Cost (Original) before opening of Tender on or before 08 August, 2019 upto 3.45 PM.**

In support of fulfilling all the essential conditions mentioned in the previous Para the contractor shall submit the details, mentioning the name of work, estimated cost, tendered amount, gross value of work done, date of commencement as per agreement & actual date of completion as per agreement along with schedule of quantities executed and any penalty levied due to delay in executing the work from an officer not below the rank of Executive Engineer (Civil).

2. The estimated cost of the work is **Rs. 14, 86,647.00** (Rupees Fourteen Lakh Eighty Six Thousand Six Hundred Forty Seven only).
3. Period for completion of the work will be **60 Days** and the date of commencement shall be reckoned from the seventh day of issue of award letter.
4. The tender documents can be made available for viewing only at NISER website www.niser.ac.in.
5. Tenders can only be viewed from website www.niser.ac.in. The cost of tender document (Non-transferable) shall be submitted along with the technical bid. Please note that tender documents are not transferable. Tender can be downloaded and bided from website address: www.tenderwizard.com/NISER.
6. Tender documents are to be uploaded in two parts. The First part shall consist of the technical Bid including the cost of tender, EMD and the documents in support of eligibility criteria. The second part shall contain the financial bid showing the detail schedule of work. **Tenders complete in all respects, will be accepted through online up to 12.30 PM on 08 August 2019. The Tender shall be opened at 04.00 PM on 08 August 2019.** Please note, that bids submitted without tender cost and EMD are summarily being rejected. The bidder those who will not submit the self-attested hard copies of required documents in the office, the technical bid of the bidder will not be opened.
7. The Earnest Money amounting to **Rs. 29,733.00 (Rupees Twenty Nine Thousand Seven Hundred Thirty Three only)** as demand draft or pay order from any scheduled Bank and drawn in favor of the **Director, NISER** should be deposited along with the tender documents.

Tender received without earnest money will be invalid and rejected as this is purely construction work.

8. Director, NISER does not bind himself to accept the lowest or any tender and reserves the right to accept the tender either in whole or in part of the tender and the tenderer shall be bound to perform the same at the rates quoted. The decision of the Director shall be final in this regard.
9. Canvassing in connection with the tenders is prohibited and the tenders submitted by the contractor who resort to canvassing are liable for rejection.
10. The tenderer shall not be permitted to tender for works in the concerned unit of DAE in which a relative is posted in the grade between Controller of Administration and Scientific Assistant (both inclusive). He shall also intimate the names of persons who are working with him in any capacity or subsequently employed by him and who relatives are as mentioned above.

NOTE:- A person shall be deemed to be a relative of another if, (a) they are members of a Hindu undivided family; or (b) they are husband and wife; or (c) the one is related to the other in the following manner : Father, Mother (including step mother), Son (including step son), Son's wife, Daughter (including step daughter), Father's father, Son's son, Son's Son's wife, Son's daughter, Son's daughter's husband, Daughter's husband, Daughter's son, Daughter's son's wife, Daughter's daughter, Daughter's daughter's husband, Brother (including step brother), Brother's wife, Sister (including step sister), Sister's husband.

11. The Bid shall remain valid for a minimum period of 75 days from the date of opening of the tender for the purpose of acceptance and award of work. Validity beyond 75 days from the date of opening shall be by mutual consent.
12. The tenderer should see and obtain the drawings. In case of any queries, necessary clarifications may please be sought from the office of the Scientific Officer-D (Civil). No claim whatsoever will be entertained in this regard for any alleged ignorance thereof.
13. **Performance Guarantee** is liable to be forfeited if the contractor fails to commence the work as per award letter.
14. Some of the provisions of the contract are given below.
 - a) **DEFECT LIABILITY PERIOD** - Twelve months from the date of completion as certified by the authorized engineer.
 - b) **MINIMUM VALUE OF WORK FOR THE INTERMEDIATE CERTIFICATE**
Intermediate certificate for a lesser amount can be admitted for payment at the discretion of the Institute.
 - c) **SECURITY DEPOSIT** - A sum @ 2.5% of the gross amount of the bill shall be deducted from each running bill of the contractor, till the sum amount to security deposit of 2.5% of the tendered value of the work. In addition, the contractor shall be required to deposit an amount equal to 5% of the tendered value of the contract as **Performance Security** within the period prescribed for commencement of work in the letter of award issued to him.
 - d) **COMPENSATION** – In the event of any delay in completion of the work beyond the scheduled period, the contractor shall pay an amount equal to **one per cent** of the total cost of work or such smaller amount as decided by Director, NISER (whose decision shall

- be final) as compensation to the institute, for every week that the work remains un-commenced or unfinished. Compensation to be paid shall not exceed **ten per cent of the estimated cost** of the total work as per award letter.
15. Stores to be issued: - No material shall be issued by the Institute. The responsibility for arranging all materials from approved manufacturer as per award letter lies with the contractor.
 16. Taxes as applicable will be deducted from every RA bill and also from the final bill of the contractor at the rate prescribed by govt. of India from time to time.
 17. The price quoted are inclusive of all taxes and duties and no taxes or duties will be paid extra. The Payment will be processed after the satisfactory completion of the work.
 18. Escalation cost will not be given for the work which the stipulated period of completion is 18 (Eighteen) months or less.
 19. The successful bidder will be required to inform the names, qualifications and experiences of the supervising staff to be deployed for execution of the work. In case of any changes occurring during the course of execution of the said work, the same shall also be intimated by the bidder to the institute.
 20. The Contractor shall have to make his own arrangements for storage of materials required for execution of the work and NISER in any manner shall not be held responsible for the storage and safe custody of the said materials at work site.
 21. Water charges @1% will be deducted from the Contractor's bill.
 22. The power will be supplied on request at one point within 50 meter of the building premises. The contractor shall install his own main switch, energy meter, cables, electric board/switch room etc. of adequate capacity and of suitable type to receive, control and further distribute the power involved. The exact location and further details about the supply point will on receipt of the contractor's application be decided upon by the Department, whose decision in the matter will be final and binding. The total final connected load and the anticipated maximum demand shall be furnished by the contractor about one month in advance of the actual initial requirement and for any addition in load subsequent to initial supply, at least one week's notice from the date of submission of installation test report for the said additional load will be given. The electricity charges will be deducted from the contractor's bill as per actual meter reading.
 23. At the time of starting the work the contractor has to inform the list of tools and plants brought to the site work. No items other than the list submitted will be allowed to be taken out of the site.
 24. The work should be executed during day time only for safety reason.
 25. Tenderers shall inspect and examine the site and its surroundings and satisfy themselves before submitting their tenders as to the nature of the site and shall

themselves obtain all necessary information as to risks, contingencies and other circumstances which may influence or affect their tender. A tenderer shall be deemed to have full knowledge of the site whether he inspects it or not. Submission of a tender implies that the tenderer has read the complete contract documents and is aware of the conditions, specification of the work to be done and of the local conditions and other factors having a bearing on the execution of work. Any claim either for extra amount or for additional time for execution due to ignorance about the site and working condition is not payable.

26. It is the sole responsibility of the tenderer to ensure proper lightning/visibility, access (ladder etc.) and any other safety measures for the trained personnel during work.
27. The work will be executed as per CPWD, DAE procedure of work and direction of Engineer-In-charge.
28. All the materials shall be tested and inspected in the presence of Department of their representative. Test certificates of all components shall be made available for approval of the Department.
29. No materials/equipment shall be shipped to site unless it is inspected, tested and certified for acceptance by the Department or their representative at factory as per latest additions IS, BS and other applicable standards.

Faculty In Charge
Institute Works Department, NISER



National Institute of Science Education and Research, JATNI
Bill of Quantities

**Notice Inviting E-Tender No.- DTCN No. NISER/ IWD-Civil/Academic/2019-20/09, Dated:
29.07.2019**

**Provision of Dry wall partition and aluminum partition for CIS department at Library
Building, NISER, Jatani**

Name of the Vendor					
Sl. No.	Description of Items	Unit	Quantity	Rate in Figures	Amount
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For fixed portion. Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15).	Kg	1436.55		0.00

2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, door handle of approved make all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For shutters of doors, windows & ventilators including providing and fixing hinges / pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required. Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	Kg	198.45		0.00
3	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineer-in-Charge. Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side	Sqm	196.64		0.00
4	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineerin- Charge. (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5.5 mm thickness.	Sqm	57.90		0.00
5	Providing and fixing Anodised Aluminium handles 125 mm with plate 175 x 32 mm with SS screws etc. complete as per direction of Engineer-in-Charge. Anodized (AC 15) aluminium	Nos	18.00		0.00
6	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm), with double speed adjustment with necessary accessories and screws etc. complete	Nos	10.00		0.00
7	Providing and fixing 100 mm brass locks (best make of approved quality) for aluminium doors including necessary cutting and making good etc. complete.	Nos	10.00		0.00

8	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete. Single rubber stopper	Nos	10.00		0.00
9	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with necessary screws etc. complete: 250x10 mm	Nos	15.00		0.00
10	Supply and Installation of 70 mm thick magnesium oxide board drywall Tufbloc partition system having (high water & fire resistance) which includes two layers of tufbloc magnesia square board having square edge & size 2400 X 1200 x 10 mm to be fixed on the either side of the GI stud channel framework in horizontal position of length side board. Now the frame work includes Floor / Head (FC 50) channels having thickness 0.06 mm length 3600 mm ,equal flanges of 32 mm & web of 50 mm fixed to floor & ceiling with suitable fasteners at 300 mm centers staggered noise & fire rated silicon sealant to caulked along the perimeter of the partition frame before fixing channels.Then stud channels SC 48 having thickness 0.75 length 3600 mm , un equal flanges of 36 mm & web of 48 mm should be placed into the floor / head channels positioned vertically at 600 mm centers. Horizontal intermediate channel at 1200 mm centers to locked with the vertical studs. Extra reinforcement to be provided at openings (doors & Window). Apply Synthetic poly fiber 10 x 25 is 50 mm width,600/1200 mm density 1000 gsm filled between the studs & held in position by using chicken mesh wire / pasting on the board. Now, boarding is to done on each side of studs framework in a staggered pattern by the help of self drilling screw at 300 mm centers. After boarding of two boards jointing & finishing is to be done by joint compound . The flush look will appear after sanding the two boards joint properly to get a smooth look . The technical parameters of the boards - Density- 1000 kg / mt cube weight 10 kg/ mt sq , Fire -150 min acoustic STC - 50 db, climate OCRH - 50 ,99 Termite resistance - yes, Moister absorbent - 6.8% after 2 hr, wet expansion less than -0.02% from ambient to saturation ,Moister Movement - 0.02% Green - RC % - 30 Strength - Anti sag. Test reports of manufactures are to submitted at the time of delivering of materials.	Sqm	93.92		0.00
11	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed. All kinds of soil	Cum	2.01		0.00
12	Supplying and filling in plinth with Jamuna sand under floors, including watering, ramming consolidating and dressing complete.	Cum	0.36		0.00
13	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	Cum	0.75		0.00
14	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in : Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum	2.10		0.00

15	12 mm cement plaster of mix: 1:4 (1 cement : 4 fine sand)	Sqm	20.00		0.00
16	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	369.20		0.00
17	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	Sqm	28.20		0.00
18	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface: Water thinnable cement primer	Sqm	20.00		0.00
19	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture	Sqm	30.00		0.00
20	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. Two coats	Sqm	382.00		0.00
21	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre	Sqm	382.00		0.00
Total					0.00